

# Central Coast Engineers, Inc.

P.O. Box 2503, Salinas, CA 93902

Tel (831) 757-5554, Fax (831) 757-2226

February 11, 2021

RE: Revised Drawings & Specifications  
Spreckels Park Restrooms  
Spreckels Memorial Park  
Spreckels, CA 93962

## DRAWING ADDENDUM

### ARCHITECTURAL

- A2.1 New Sheet for new walkway.
- A2.2 Added new walkway all around building.  
Added landscape curb 2 sides of drinking fountain.  
Added down spouts.
- A2.3 Added new gutters and downspouts.  
Corrected roof call outs, to include battens.
- A3.1 Revised Finish Legend
- A4.1 Revised Finish Schedule

### PLUMBING

- P1.1 Added trap primer and clean out to floor drains.  
Added exterior clean outs.  
Added point of connection for water and waste lines.  
Added water shut offs.  
Added water line sizes.

## ELECTRICAL

E1.1 Added exterior light controls.

Added new sub panel.

Corrected light fixture schedule.

Added core drill call out for hand dryer conduit / junction box.

## STRUCTURAL

S3.2. Added new detail sheet.

S2.2 Corrected roof framing notes.

Added kickers to hip.

## PROJECT MANUAL ADDENDUM

### REVISED SPECIFICATIONS

- |  |  |
|--|--|
| Item 20. Replace Exhaust Fan Panasonic WhisperSense DC   | FV0511VQC1                                   |
| Item 21. Replace Interior lighting with Eaton Fail Safe FMSLED   | FMS-D12-2-LD4-<br>2STD-40-120-<br>93/96-EDD1 |
| Item 27. Replace Floor Finish with<br>SW Fas Top 12SL Self Leveling Urethane Slurry System<br>APPLICATION:<br>Primer 3477.<br>Slurry @ 1/8" Color Dark Gray<br>Broadcast Standard Dry Silica Sand 20-40 mesh 4080, 5035, 5310-8<br>Seal Coat 4090TC, 5095<br>Topcoat: 1ct GP 3746, 1-2 cts GP 4850 |  |

## ADDED SPECIFICATIONS

### Item 34. Floor Base SW Epoxy Cove Base System

SW General Polymers 3561

APPLICATION: Primer 3561V

Binder Resin 3561

Grout Coat 3745

Seal Coat 3745

### Item 35. Interior Wood Framed Wall Finish

DensArmor Plus Fireguard 5/8" Gypsum Panels (Smooth finish at joints or skim coat joint compound over entire surface of panels to reduce highlighting).

1ct. SW Pro Mar 200 Zero VOC primer

2ct. SW Pro-Ind. Pre-Catalyzed Epoxy Gloss

Color – SWOO55 Light French Gray

### Item 36. Interior Concrete Block Wall Finish

2 ct. SW Pro-Ind Pre-Catalyzed Epoxy Semi-Gloss

Color – SWOO55 Light French Gray

### Item 37. Exterior Concrete Block Wall Finish

1 ct. SW Loxon Concrete Masonry Primer Sealer

2ct SW Pro-Industrial Acrylic Semi-Gloss

Color SW2850 Chelsea Gray

### Item 38. Ceiling Finish DensArmor Plus Fireguard 5/8" Gypsum Panels

1 ct. SW Pro-Ind. Pro-Cryl Primer

2ct SW Pro-Industrial Acrylic Semi-Gloss

Color SW7104 Eider White

### Item 39. Boral Roofing Slate Saxony 900 Hartford

Color Stone Mountain Blend

### Item 40. Alan Block AB- Classic Collection Landscape Wall