



# AUSONIO

I N C O R P O R A T E D

11420A Commercial Parkway  
Castroville, CA 95012  
www.ausonio.com

Telephone (831) 633-3371  
Upstairs Fax (831) 633-4004  
Downstairs Fax (831) 633-3389

11420 A Commercial Parkway  
Castroville, CA 95012  
Ph : (831) 633-3371

*RFI*

**To:** Paul J. Ingram  
Spreckels Memorial District  
90 Fifth Street  
Spreckels, CA 93962  
Ph: (831)455-7855

**RFI #:** PB-011

**Date:** 2/8/2021

**Job:** D21015 Spreckles Memorial Park ADA

**Phone:**

**CC:**

**Subject:** Pre-Bid RFI #011 - Resinous Wall System

**Drawing:** A4.3

**Spec Section:**

**Cost Impact:** TBD

**Schedule Impact:** TBD

**Request:**

**Date Required:** 2/11/2021

Details 5 & 6 on sheet A4.3 calls out a resinous wall system. Please provide clarification and specifications.

**Requested by:** Roxanne Cheysson

**Response:**

Finish Schedule on sheet A4.1

Paul J. Ingram


Answered By

Spreckels Memorial District


Company

3/2/2021


Date




**A MEN'S INTERIOR ELEVATION**  
SC: 1/2"=1'-0"




**C MEN'S INTERIOR ELEVATION**  
SC: 1/2"=1'-0"




**B MEN'S INTERIOR ELEVATION**  
SC: 1/2"=1'-0"




**D MEN'S INTERIOR ELEVATION**  
SC: 1/2"=1'-0"




**E WOMEN'S INTERIOR ELEVATION**  
SC: 1/2"=1'-0"



**G WOMEN'S INTERIOR ELEVATION**  
SC: 1/2"=1'-0"



**F WOMEN'S INTERIOR ELEVATION**  
SC: 1/2"=1'-0"



**H WOMEN'S INTERIOR ELEVATION**  
SC: 1/2"=1'-0"

## FINISH SCHEDULE

**F.1** PARTITIONS: ASI GLOBAL PARTITIONS:  
FOLKSTONE GRAY 9400 SOLID PLASTIC

**F.2** INTERIOR CONCRETE FLOOR:  
SW FasTop 12SL Self-Leveling Urethane Slurry System  
APPLICATION: Primer 3477  
Slurry @ 1/8" (Color Dark Gray) Broadcast Standard Dry  
Silica Sand 20-40 mesh 4080, 5035, 5310-8  
Seal Coat 4090TC, 5095  
TOP COAT: 1ct GP 3746, 1-2 cts GP 4850


**F.3** INTERIOR FLOOR BASE: SW EPOXY COVE BASE SYSTEM  
SW GENERAL POLYMERS 3561  
APPLICATION: Primer 3561V  
Binder Resin 3561V  
Grout Coat 3745  
Seal Coat 3745

**F.4** INTERIOR WOOD FRAMED WALL W/ DensArmor Plus  
Fireguard 5/8" GYPSUM PANELS  
(Smooth finish at joints or skim coat joint compound  
over entire surface of panels to reduce highlighting)  
1ct. SW PRO-MAR 200 ZERO VOC PRIMER  
2cts. SW PRO-IND. PRE-CATALYZED EPOXY GLOSS  
\*COLOR- SW0055 LIGHT FRENCH GRAY

**F.5** INTERIOR CONCRETE BLOCK WALL:  
2cts. SW PRO-IND. PRE-CATALYZED EPOXY SEMI-GLOSS  
\*COLOR- SW0055 LIGHT FRENCH GRAY

**F.6** EXTERIOR CONCRETE BLOCK WALL:  
1ct. SW LOXON CONCRETE MASONRY PRIMER SEALER  
2cts. SW PRO-INDUSTRIAL ACRYLIC SEMI GLOSS  
\*COLOR-SW2850 CHELSEA GREY

**F.7** CEILING W/ DensArmor Plus Fireguard 5/8" GYPSUM PANELS  
1ct. SW PRO-IND. PRO-CRYL PRIMER.  
2cts. SW PRO-IND ACRYLIC PAINT (EIDER WHITE INTERIOR  
SEMI-GLOSS SW7104 MILDEW-RESISTANT)



## FIXTURE/EQUIPMENT SCHEDULE

- ADA COMPLIANT WATER CLOSET; METCRAFT  
• ELONGATED BOWL.  
• HEAVY DUTY HIGH POLISHED INTEGRAL SEAT,  
NO COVER; TOILET SEAT.  
• SLOAN SENSOR FLUSHOMETER,  
SLOAN 8111-1.28 GPF
- ADA COMPLIANT URINAL; METCRAFT  
• HEAVY DUTY STAINLESS STEEL  
• SLOAN G2 SENSON FLUSHOMETER,  
G2 8186-05 GPF
- ADA COMPLIANT LAVATORY; METCRAFT  
• RECTANGULAR BASIN  
• TOUCHLESS FAUCET; Z6950-XL-S;  
0.5 gal/min AT 60psi
- HIGH SECURITY MIRROR; METCRAFT - A752
- JANITOR SINK; METCRAFT MOP SINK 6390-2  
• 12" HIGH STAINLESS STEEL WALL SHIELD  
• FAUCET: ZURN Z842H1-XL
- WATER FOUNTAIN/BOTTLE FILLING/ PET STATION:  
ELKAY MODEL LK4420BF1UDBFRK  
FINISH EVERGREEN (EVG)
- ADA COMPLIANT HAND DRYER: WOLD DRYER  
VERDeDi  
• AUTOMATIC SURFACE MOUNTED  
• STAINLESS STEEL
- TISSUE DISPENSER; METCRAFT: Item# A723-1  
• STAINLESS STEEL  
• DUAL ROLL HOLDER
- GRAB BARS; METCRAFT:  
a. Item# A551 36" LONG  
b. Item# A552 42" LONG
- SEAT COVER DISPENSER:  
ULINE Item# H-1592 CHROME SEAT COVER.
- SANITARY NAPKIN RECEPTACLE:  
ULINE Item# H-3454 - STAINLESS STEEL
- FOAMING SOAP AUTO DISPENSER:  
ULINE Item# H-3415
- CHANGING TABLE:  
KOALA KARE Item# KB200-01SS GREY  
HORIZONTAL WALL MOUNTED BABY CHANGING TABLE
- OUTLET LOCKING COVER: LEGRAND WP26L
- EXIT SIGN W/ EMERGENCY LIGHTS  
ULINE H-6509 RED
- ELECTRIC TANKLESS WATER HEATER:  
AO Smith C2VA-120E  
UEF= 0.84

REVISIONS	BY
1 PLAN CHECK 12-22-20	D.J.
2 ADDENDUM 2-09-21	D.J.
<div> <div> </div> <div> <b>STRUCTURAL DESIGN</b>  <b>CCE</b>  CENTRAL COAST ENGINEERS, INC.  P.O. BOX 25032  SAN JOSE, CA 95128  P 831.757.5554  F 831.757.2226 </div> </div>	
<div> <div> PROJECT TITLE:  <b>ADA UPGRADE:</b>  <b>SPRECKELS MEMORIAL PARK</b>  CORNER OF LLANO AVE. &amp; SECOND ST.  60 LLANO AVE. SPRECKELS, CA 93962  APN # 177-056-001-000 </div> <div> SHEET TITLE:  <b>FIXTURE AND EQUIPMENT PLAN</b>  <b>INTERIOR ELEVATIONS</b> </div> </div>	
JOB No. CCE-19-101	
DATE: 9/2/2020	
SCALE: AS NOTED	
DRAWN BY: VRA	
SHEET No.:	
<b>A4.1</b>	
# OF SHEETS	